



TOTAL PERIMETER:	$65'-0'' \times 2$ $\frac{54'-8'' \times 2}{239'-4''}$
8' WALL:	25'
9' WALLS:	215'
WALL AREA:	2,135 sq.ft.
WINDOWS & DOORS:	-511 sq.ft.
FRONT GABLES:	24 sq.ft.
BACK GABLE:	176 sq.ft.
WALL STUCCO:	1,824 sq.ft.
FIVE POSTS, 14"x14":	200 sq.ft.
TOTAL STUCCO:	2,024 sq.ft. = 225 sq.yd.
WINDOWS & DOOR FOAM:	116 lin.ft.

PROJECT:	BEFFA REMODEL	
LOCATION:	20917 GREENLEAF DR.	
TITLE:	STUCCO AREAS	
DATE:	JUL/16/2011	
DRAWING:	MIHAI BEFFA	
SHEET:	1 of N	SCALE: N/A